

SECTION 07 42 29

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes, but is not limited to, the following:
1. Extruded solid, single wall terracotta panels.
 2. Aluminum horizontal support framing.
 3. Mechanical anchors and fasteners utilized for the installation of the system
 4. Miscellaneous anchors, fasteners, insulation, air and moisture barrier, vertical sheathing, metal trim, and accessories provided under other Sections
- B. Related Sections include the following:
1. Division 05 Section "Cold-formed Metal Framing".
 2. Division 06 Section "Sheathing"
 3. Division 07 Section "Thermal Insulation"
 4. Division 07 Section "Water-Resistive Barriers/Weather Barriers" and/or "Fluid-Applied Waterproofing".
 5. Division 07 Section "Sheet Metal Flashing and Trim"
 6. Division 08 Section "Entrances and Storefronts"
 7. Division 08 Section "Steel Windows"

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
1. Meet with Owner, Architect, Owner's insurer if applicable, terracotta panel rainscreen wall system Installer, structural-support Installer, and installers whose work interfaces with or affects terracotta wall panel rainscreen wall system.
 2. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 1

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|-----------------------------|-----------------------------|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |

3. Review methods and procedures related to terracotta panel rainscreen wall system installation, including manufacturer's written instructions.
4. Examine support conditions for compliance with requirements, including alignment between and attachment to structural members.
5. Review flashings, special details, penetrations, openings, and condition of other construction that affect the terracotta panel rainscreen wall system.
6. Review governing regulations and requirements for insurance, certificates, and tests and inspections if applicable.
7. Review temporary protection requirements for the terracotta panel rainscreen wall system, during and after installation.
8. Review procedures for replacement of terracotta panels damaged after installation.
9. Document proceedings, including corrective measures and actions required, and furnish copy of record to each participant.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.
- B. Shop Drawings:
 1. Include fabrication and installation layouts of terracotta panel rainscreen wall system components; details of edge conditions, joints, panel profiles, corners, anchorages, and attachment components; and special and unique details.
 2. Accessories: Include details of the flashing, trim and anchorage at a scale of not less than 1-1/2 inches per 12 inches. Indicate metal trims, flashings, closures, and accessories that are furnished by other trades to provide dimensional requirements that may affect the terracotta panel rainscreen system.
- C. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
 1. Terracotta Panels: 6 inches long by actual panel module height. Include installation support framing, fasteners, and other metal accessories furnished by the terracotta manufacturer for the terracotta panel rainscreen wall system.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each product, tests performed by a qualified testing agency.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 2

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

- C. Field quality-control reports.
- D. Sample Warranties: For special warranties.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For terracotta panels to include in maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Manufacturer Qualifications: A terracotta wall panel rainscreen wall system manufacturer capable of manufacturing extruded, solid, single wall terracotta panels, and its support components, that meet or exceed the performance requirements indicated and of documenting this performance by test reports and calculations.
- C. Source Limitations: All primary products specified in this section will be supplied by a single manufacturer, experienced in designing and manufacturing terracotta panel rainscreen wall systems
- D. Mockups: Build mockups as detailed and shown in the Contract Documents to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
 1. Build mockup of typical terracotta panel rainscreen wall system, including, supports, attachments, and accessories.
 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, terracotta panels, and other manufactured items so as not to be damaged or deformed. Package metal terracotta panels for protection during transportation and handling.
- B. Unload, store, and erect terracotta panel rainscreen wall system in a manner to prevent breakage, chipping, and surface damage.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 3

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

- C. Store products in manufacturer's unopened packaging, covered with suitable weathertight and ventilated covering, until ready for installation. Do not store terracotta panel rainscreen wall system components in contact with other materials that might cause staining, chipping, breakage, or other surface damage.

1.9 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of terracotta panel rainscreen wall system to be performed according to manufacturers' written instructions and warranty requirements.

1.10 COORDINATION

- A. Coordinate terracotta panel rainscreen wall system installation with moisture drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a ventilated, secure, and noncorrosive installation while maintaining the continuity of the weather barrier.

1.11 WARRANTY

- A. Special Material Warranty: Manufacturer's standard form in which manufacturer agrees to furnish components of the terracotta panel rainscreen wall system that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:
 - a. Structural failures including aspects of terracotta performance defined in ASTM C67.
 - b. Deterioration of terracotta and other materials beyond normal weathering.
2. Warranty Period: Ten years from date of Substantial Completion.

- B. Special Installation Warranty: Installation Contractor's standard form in which installer agrees to repair or replace components of the terracotta panel rainscreen wall system that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:
 - a. Structural failures including aspects of terracotta performance defined in ASTM C67.
 - b. Installation failures including movement of terracotta panels caused by the movement within the terracotta panel rainscreen wall system installation.
 - c. Deterioration of terracotta and other materials beyond normal weathering.
2. Warranty Period: Two years from date of Substantial Completion.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 4

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|-----------------------------|-----------------------------|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |

1.12 EXTRA MATERIALS

- A. Furnish extra materials that match the products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Terracotta panel rainscreen wall system horizontal support framing: For each type, the lesser quantity of 40 linear feet or 1% of the installed quantity.
 2. Terracotta panels: For each surface texture, the lesser quantity of 30 or 1% of the installed quantity. The panels shall be provided in the longest length dimension installed on the project.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide terracotta panel rainscreen wall system capable of withstanding the effects of the following loads, based on testing according to ASTM E330:
1. Wind Loads: As indicated on Drawings.
 2. Other Design Loads: As indicated on Drawings.
 3. Loads stipulated by the Authorities and Building Codes having Jurisdiction.
 4. Deflection Limits: For wind loads, no greater than 1/200 of the span.
- B. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
1. Temperature Change (Range): 100 deg F, ambient; 180 deg F, material surfaces.

2.2 TERRACOTTA PANEL RAINSCREEN WALL SYSTEM PANELS

- A. Terracotta Panel System: Provide factory-extruded solid, single wall terracotta panels formed into profile for installation method indicated. Include attachment assembly components and accessories required.
1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include the following:
 - a. Terreal North America LLC, A Subsidiary of Ludowici Roof Tile. (telephone: 888-582-9052)
 - b. Boston Valley Terra Cotta USA.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 5

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

- c. NBK.
- B. Basis-of Design Terracotta Wall Panels: Zephyr Evolution terracotta.
 - 1. Panel Thickness: 9/16 inch, nominal.
 - 2. Panel Vertical Module Dimension: 12 inch.
 - 3. Panel Horizontal Module Dimension: as indicated on Drawings.
 - 4. Panel Weight: 7.5 pounds per square foot.
 - 5. Vertical Joint Type: Open joint without metal trims or gaskets.
 - 6. Horizontal Joint Type: Overlapping, ship-lap type.
 - 7. Panel Configuration: Solid, single wall per manufacturer's standard extruding process.
 - 8. Finish Panel Production Tolerances:
 - a. Squareness: +/- 3mm.
 - b. Straightness of Panel's Top Edge: Color: +/- 3mm.
 - c. Flatness of Panel Height: +/- 2mm.
 - d. Flatness of Panel Length: +/- 3mm.
 - 9. Color: Through-body (Champagne) (Chocolate Brown) (Dark Grey) (Ebony) (Pearl Grey) (Red) (Red-Orange) (Sahara Beige) (Salmon Pink) (Stone) (Violine).
 - 10. Exterior Finish/Texture: Smooth) (Ribbed) (Sanded).
- C. Attachment Assembly: Rainscreen principle system that does not require gaskets and/or metal trims to hold the terracotta panels in proper alignment.

2.3 TERRACOTTA WALL PANEL ATTACHMENT COMPONENTS

- A. General: All metal supporting members shall be fabricated from 6063 Alloy Aluminum for resistance to corrosion.
- B. Horizontal Support Profile:
 - 1. Material: 6063 Alloy Aluminum
 - 2. Thickness: As required for structural performance of the terracotta panel rainscreen wall system, per manufacturer's standard installation requirements.
 - 3. Finish: Manufacturer's standard.
 - 4. Configuration: Channel shape with support legs and weep holes per manufacturer's standard installation requirements
 - 5. Member Depth: Manufacturer's standard.
 - 6. Member Vertical Spacing: 12 inches.
- C. Adhesive:
 - 1. Material: As recommended by terracotta manufacturer's written instruction and recommendations for installation.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 6

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

2. Utilized as a lateral movement restriction component within the overall system performance and not a vertical gravity load resistance component for the terracotta panels.

D. Fasteners:

1. Material: 304 Stainless Steel.
2. Type: Hex head, self-drilling.
3. Size: Manufacturer's standard required for structural performance of the terracotta panel rainscreen wall system.

2.4 MISCELLANEOUS MATERIALS

- A. Flashing and Trim: Shall be aluminum material complying with the performance criteria specified and designed to allow adjustments of the system prior to being permanently installed. These items shall be shop fabricated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. It is the responsibility of the Installation Contractor to examine the structure scheduled to receive the terracotta panel rainscreen wall system and verify that it is capable of supporting the loads from the Work specified in this section. Note deficiencies immediately and do not proceed with erection of terracotta panel rainscreen wall system until such deficiencies have been corrected or addressed by the Architect.
- B. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances for the terracotta material panel supports, and other conditions affecting performance of the Work.
 1. Examine wall framing to verify that girts, angles, channels, and other structural panel support members and anchorage have been installed within alignment tolerances required by terracotta wall panel manufacturer's written installation instructions.
 2. Examine wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by terracotta wall panel manufacturer's written installation instructions.
 - a. Verify that air- and/or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration prior to the commencement of work.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 7

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

- C. Examine roughing-in for components and assemblies penetrating terracotta panels to verify actual locations of penetrations relative to terracotta panel rainscreen wall system support framing and joints before commencement of work.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Coordinate terracotta panel rainscreen wall system with rain drainage work; flashing; trim; and construction of soffits, roofing, parapets, walls, and other adjoining work to provide a secure and noncorrosive installation.

3.3 TERRACOTTA PANEL INSTALLATION

- A. General: Comply with the system manufacturer’s written instruction and recommendations for installation as they apply to project conditions and supporting substrates in the orientation, sizes, and locations indicated on Drawings. Anchor system and other components of the Work securely in place, with provisions for thermal and structural movement.
 1. Shim or otherwise plumb horizontal support profiles from installed substrates scheduled to receive the terracotta panel rainscreen system.
 2. Field cutting of terracotta panels is not permitted except to accommodate components and assemblies penetrating terracotta panels, or form corners as detailed in the shop drawings.
 3. Do not begin installation until air- and/or water-resistive barriers and flashings that will be concealed by the terracotta panel rainscreen wall system are installed.
 4. Install flashings and trims as terracotta panel rainscreen wall system work proceeds.
 5. Align edges of terracotta panels with adjacent terracotta panels as indicated on shop drawings.
- B. Fasteners:
 1. Use stainless-steel fasteners for surfaces exposed to the exterior; use stainless steel, aluminum, or galvanized-steel fasteners for surfaces exposed to the interior per the terracotta manufacturer’s written recommendations.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by manufacturer of dissimilar metals.
- D. Attachment Assembly, General: Install attachment assembly required to support terracotta wall panels and to provide a complete rainscreen wall system, including horizontal support framing.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 8

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

1. Install aluminum support framing plumb and level in locations indicated on approved shop drawings and the terracotta panel rainscreen wall system manufacturer's written recommendations.
 2. Install support framing to allow for installation of flashings, trims, and accessories per the approved shop drawings and the terracotta panel rainscreen wall system manufacturer's written recommendations.
 3. Support framing members may be shimmed from the face of the air/water-resistive barriers and/or sheathing per the terracotta panel rainscreen wall system manufacturer's written recommendations.
- E. Installation: Install terracotta wall panels on supports at locations and spacings to achieve performance requirements specified and per the terracotta panel rainscreen wall system's approved shop drawings and manufacturer's written instructions and recommendations.
1. Do not install broken, chipped, cracked, or otherwise damaged terracotta wall panels.
 2. Install terracotta panels to maintain the horizontal and vertical reveal spacing defined on the approved shop drawings and per the terracotta panel rainscreen wall system manufacturer's written instructions and recommendations.
 3. Install adhesive along bottom attachment extruded profile per approved shop drawings and terracotta manufacturer's written installation instructions per the terracotta panel rainscreen wall system manufacturer's written instructions and recommendations.
 4. Do not apply sealants to joints unless otherwise indicated.
- F. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.
1. Install exposed flashing and trim that is without buckling and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to result in waterproof performance.
 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet with no joints allowed within 24 inches of corner or intersection. Where lapped expansion provisions cannot be used or would not be sufficiently waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with mastic sealant (concealed within joints).

3.4 ERECTION TOLERANCES

- A. Shim and align metal support framing to allow the final terracotta wall panel assembly to be plumb, true, untwisted, and in assembly plane.
- B. Installation Tolerances: Measurements are taken on the final installed exposed surface to view. Installation tolerances shall be defined as:

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 9

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|--|--|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |
| W www.hvgfacades.com.au | E info@hvgfacades.com.au | F HVG Façade Solutions | | ABN 75 104 808 853 |

1. Plumb: 1/8" in 10 feet, 1/4" in 40 feet, non-cumulative
2. Level: 1/8" in 20 feet, 1/4" in 40 feet, non-cumulative
3. Alignment & Offsets: limit to 1/8"

3.5 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect completed terracotta panel rainscreen wall system installation, including accessories.
- B. Terracotta panels will be considered defective if they do not pass test and inspections as defined in the manufacturer's written warrantee.
- C. Additional tests and inspections, at Contractor's expense, are performed to determine compliance of replaced or additional work with specified requirements.
- D. Prepare test and inspection reports.

3.6 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if applicable, as terracotta panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of terracotta panel rainscreen wall system installation, clean finished surfaces as recommended by terracotta manufacturer. Maintain in a clean condition during construction.
- B. Cleaning: No cleaning treatment or chemicals should be applied to the terracotta panels without the manufacturer's written authorization. Clean soiled areas with materials that will not damage or harm the terracotta panels or adjacent materials. Mild detergents approved by the terracotta manufacturer in writing with a soft natural bristle brush may be used
- C. After terracotta panel rainscreen wall system installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.
- D. Replace terracotta panels that have been damaged or have deteriorated beyond successful repair.
- E. Protect installed products from contact with contaminating substances resulting from construction operations. In addition, monitor terracotta surfaces that are adjacent to exterior concrete and masonry surfaces during construction for presence of dirt, scum, alkaline deposits, stains, or other contaminants. If contaminating substances do contact the terracotta surface, remove contaminants immediately per the terracotta manufacturer's written instructions and recommendations.

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 10

| MELBOURNE | SYDNEY | BRISBANE | ADELAIDE | PERTH |
|-----------------------------|-----------------------------|--------------------------------|-----------------------------|------------------------------|
| 25 West Park Drive | 29 Henderson Street | 128 - 132 Mica Street | 57-63 Barnes Avenue | 72 Bushland Ridge |
| Derrimut VIC 3030 Australia | Turrella NSW 2205 Australia | Carole Park QLD 4300 Australia | Marleston SA 5033 Australia | Bibra Lake WA 6163 Australia |
| T (03) 9394 3130 | T (02) 8525 6900 | T (07) 3718 2360 | T (08) 8113 6000 | T (08) 9494 0100 |
| F (03) 9394 3129 | F (02) 955 6068 | F (07) 3718 2399 | F (08) 81136099 | F (08) 9494 0190 |

END OF SECTION

TERRACOTTA PANEL RAINSCREEN WALL SYSTEM

07 42 29 - 11

MELBOURNE

25 West Park Drive
Derrimut VIC 3030 Australia
T (03) 9394 3130
F (03) 9394 3129

SYDNEY

29 Henderson Street
Turrella NSW 2205 Australia
T (02) 8525 6900
F (02) 955 6068

BRISBANE

128 - 132 Mica Street
Carole Park QLD 4300 Australia
T (07) 3718 2360
F (07) 3718 2399

ADELAIDE

57-63 Barnes Avenue
Marleston SA 5033 Australia
T (08) 8113 6000
F (08) 81136099

PERTH

72 Bushland Ridge
Bibra Lake WA 6163 Australia
T (08) 9494 0100
F (08) 9494 0190

W www.hvgfacades.com.au

E info@hvgfacades.com.au

F HVG Façade Solutions

ABN 75 104 808 853